

ILORIN INNOVATION HUB BILL OF QUANTITIES

FOR

KWARA STATE GOVERNMENT

BY

SPACEFINISH AFRICA LIMITED

S

February 2022

ITEM		DESCRIPTION	AMOUNT
		Ilorin Innovation Hub General Summary	
	BILL NO 1	PRELIMINARIES	12,947,428.00
	BILL NO 2	RECEPTION	22,340,007.08
	BILL NO 3	2-MEETING ROOM	18,637,282.60
	BILL NO 4	COFFEE LOUNGE	22,617,148.78
	BILL NO 5	EVENT HALL	59,193,268.72
	BILL NO 6	CONFERENCE ROOM	24,170,446.84
	BILL NO 7	MINI MEETING ROOM	27,419,947.20
	BILL NO 8	STAFF OFFICE	28,797,150.21
	BILL NO 9	MANAGEMENT'S OFFICE	71,611,176.84
	BILL NO. 10	GENERAL WORKSPACE	29,134,696.40
		SUB-TOTAL	316,868,552.67
		ADD 7.5% VAT	23,765,141.45
		TOTAL	340,633,694.12

ITEM	DESCRIPTION	QTY	UNIT	RATE	AMOUNT
	<u>PRELIMINARIES AND GENERAL ITEMS</u>				
	<u>Visit Site and scope of works</u>				
A	The Contractor has visited and inspected the site and thoroughly completely informed as to the condition of the site in its present peculiar nature and the extent and character of the works to be means of access and storage space, the conditions affecting the labour and the availability and required services				
	<u>Restrictions in use of site.</u>				
B	The Contractor shall confine his activities and those of his work confines of the site. The Contractor shall not allow his work-people onto neighboring sites and shall be responsible for keeping from trespassing onto site. The Contractor shall not without the permission of the client and/or its team permit the loading or materials on the site outside normal working hours and shall noise to a minimum throughout the contract to avoid causing residents or occupants of adjoining or adjacent buildings and				
	<u>Care of existing installations and works</u>				
C	The Contractor will be held responsible for protecting and				
	<u>Welfare and Safety</u>				
D	The Contractor is to provide on site a FIRST AID box or cupboard				
	<u>Community Relations / Miscellaneous Expenses</u>				
E	The Contractor is to allow for community relations and This excludes all necessary statutory fees and levies				
	<u>Plants, Tools and Vehicles</u>				
	allow for providing all necessary tools and equipment required for the proper execution of the works. The Contractor shall provide without extra charge all labour and things required by the architect for testing and measuring the works and for weighing, measuring, providing or testing the efficiency of any portion of the works and shall also at his cost provide all planking, gangways etc, necessary				
F	for affording access to every part of the work.				
s					
	To Collection	=N=			

ITEM	DESCRIPTION	QTY	UNIT	RATE	AMOUNT
	<u>Preliminaries (Cont'd)</u>				
	<u>Progress Photographs</u>				
A	Allow for providing photographs taken with a digital camera from				
B	Allow for electronic transmission of progress photographs to the team as and when requested.				
	<u>Time and Progress</u>				
C	Immediately upon signing the Contract, or before signing the requested, the contractor shall in collaboration with sub-submit to the Architect for acceptance Programme and progress cover all activities on the site and shall record progress thereon the execution of the works.				
D	The Contractor shall arrange for representatives to attend site as and when reasonably required by the Architect				
	<u>Covering Up</u>				
E	No work shall be covered up until it has been examined and the Architect.				
	In case of the work executed against provisional quantities in the Quantities (and therefore subject to measurement) the Contractor notify the Consultant before proceeding to cover up the works.				
	<u>Existing Installations</u>				
F	Allow for protecting and maintaining all pipes, ducts and cables excavations, for keeping all ditches, gullies and channels clear and unobstructed and for making good any damage caused to public or roads,paths, kerbs and drains and paying all costs and charges				
	<u>Delays</u>				
G	The Contractor will be deemed to have made allowance for all caused by difficulty in obtaining labour and materials or by part or whole of the works				
	<u>Cleaning on Completion</u>				
H	Allow for cleaning down the whole of the premises including glass and cleaning off all floors, pavings, metalwork, finishing and throughout, touching up generally and removing all stains, dirt materials and rubbish and leaving the works and site in a clean condition and ready for immediate use, with all damage to paths and drains, etc, made good to the satisfaction of the				
I	Allow a provisional sum of 100% of the initial amount paid for the processing of APG				
		=N=			

ITEM	DESCRIPTION	QTY	UNIT	RATE	AMOUNT
	<u>COLLECTIONS</u> Page 1 Page 2 Page 3				12,947,428.00
	PRELIMINARIES AND GENERAL ITEMS Carried to GENERAL SUMMARY	=N=			12,947,428.00

ITEM	DESCRIPTION	QTY	UNIT	RATE	AMOUNT
	<u>INTERNAL FINISHINGS</u>				
	<u>INTERNAL WALL PARTITIONS</u>				
	<u>Sound Proof Walling</u>				
AI	100mm thick insulated soundproof partition drywalling framing built of galvanised steel framing, double faces of cement gypsum board with melamine-coating filling made of HD Rockwool to designer's specification		nr		-
	<u>Glass Partition</u>				
AII	2700mm high curtain wall with aluminium glazing frame of bronze anodized aluminium sections in approved colour, glazed with 8mm toughened/ laminated glass frosted to 1100mm height and other part maintained as plain glass including provision of sealant in the joints complete with all necessary fittings and		nr		-
	Internal partition to summary				-
	<u>Timber Door</u>				
Ai	900 x 2100mm single leaf, single swing 2 hours fire rated timber door finished in	0	nr		-
	<u>Glass Door</u>				
B	1000 x 2100mm high factory glazed aluminium double leaf door with 10mm thick plain frosted glass complete with all necessary fittings and accessories to specification	0	nr		-
	Sub-total Doors				-
	<u>Floor Finishings</u>				
Ci	Supply and install approved High traffic carpet laid on screeded levelled floor finish surface including necessary underlay and fittings to designer details.	0	m ²		-
Cii	Supply and install approved spanish tiles on existing levelled floor finish surface to specifications	205	m ²		-
	Sub-total Floor Finishings				-
D	<u>Wall Finishings</u>				
DI	<u>Wood Panelling</u>				
	25mm MDF wood panelling on blockwall / concrete wall surfaces in approved triangular design with cove backlighting to approved standard and specification by project designer to include all necessary finishes	0	m ²		-
	Plant walls	33	m ²		-
	Alluminium sheet Cladding	75	m ²		-
DII	<u>Painting and Decorations</u>				
s	Prepare and apply one mist coat and full coats of "SHEEN" or other equal and approved paint on rendered surfaces including provision for wallpaper, stencil painting and murals paper	130	m ²		-
DIII	<u>INTERNAL POP Screeding</u>				
	Plaster of paris screed rendering on plastered block surfaces and drywalling; 2 coats, width exceeding 300mm, steel trowelled and sanding on completion	130	m ²		-
DIV	<u>Art Works</u>				
	Supply and installation of space-themed time travellers sculpture/mannequins of		Sum		8,147,143.87
DV	<u>Skirting</u>				
	50mm high HDF wooden skirting	35	m		-
	Subtotal Wall Finishings				8,147,143.87
	Page/1				

ITEM	DESCRIPTION	QTY	UNIT	RATE	AMOUNT
	<u>RECEPTION</u>				
AI	<u>Ceiling Finishings</u> 9mm thick suspended gypsum board ceiling on galvanised steel framing; fixing to galvanised wire hangers,with tamper proof heads ; spot filling whole surface with slurrv and sanded including POP surface screeding .	105	m ²		-
AII	Suspended wooden strips with plants	105	m ²		-
B	Prepare and apply full coats of WHITE EMULSION" paint or other equal and approved paint on plasterboard soffit	105	m ²		-
	Subtotal Ceiling Finishings				-
C	<u>Furnitures and Fixtures</u>				
1	Reception Desk	1	nr	2,047,143.87	2,047,143.87
					-
2	Reception Task Seats	2	nr	500,000.00	1,000,000.00
					-
3	Credenza	1	nr	1,357,143.87	1,357,143.87
					-
4	UFO Couch	1	nr	2,947,143.87	2,947,143.87
					-
5	Curvy Sofa	2	nr	2,047,143.87	4,094,287.74
					-
6	Little round stools	2	nr	300,000.00	600,000.00
					-
7	Signage	6	m2	357,857.31	2,147,143.86
	Sub-total: Fittings and Fixtures				14,192,863.21
	<u>Lighting Luminaires</u>				
F	Suspended LED Circular lighting	12	nr		-
G			nr		-
	Sub-total: Lighting Luminaires				-
J	<u>Plants</u>				
1	5 foot indoor artiicial cedar topiary trees potted plants (two peace construction)	10	nr		-
	Sub-total: Lighting Luminaires				-
	Page/2				

ITEM	DESCRIPTION	QTY	UNIT	RATE	AMOUNT
	<u>RECEPTION SUMMARY</u>				
AI	<u>Internal Partitions</u>				-
AII	Doors				-
B	Floor Finishings				-
C	Wall Finishings				8,147,143.87
D	Ceiling Finishings				-
E	Fittings and Fixtures				14,192,863.21
F	Lighting Luminaires				-
G	Plants				-
					-
	<u>RECEPTION</u>				
	Carried to MAIN SUMMARY				22,340,007.08
	Page/3				

ITEM	DESCRIPTION	QTY	UNIT	RATE	AMOUNT
	INTERNAL FINISHINGS INTERNAL WALL PARTITIONS <u>Sound Proof Walling</u> 100mm thick insulated soundproof partition drywalling framing built of galvanised steel framing, double faces of cement gypsum board with melamine-coating filling made of HD Rockwool to designer's specification		nr		-
	<u>Glass Partition</u> 2700mm high curtain wall with aluminium glazing frame of bronze anodized aluminium sections in approved colour, glazed with 8mm toughened/ laminated glass frosted to 1100mm height and other part maintained as plain glass including provision of sealant in the joints complete with all necessary fittings and accessories.	40	m2	241,991.16	9,679,646.40
	Ditto; Regular Patterned Frosting	40	m2	91,346.97	3,653,878.80
	Internal partition to summary				13,333,525.20
	<u>Timber Door</u> 900 x 2100mm single leaf, single swing 2 hours fire rated timber door finished in approved	0	nr		-
	<u>Glass Door</u> 900 x 2100mm high factory glazed aluminium single leaf door with 10mm thick plain frosted glass complete with all necessary fittings and accessories to Architect's specification	2	nr	1,394,939.35	2,789,878.70
	Ditto; Regular Patterned Frosting	2	m2	1,256,939.35	2,513,878.70
	Sub-total Doors				5,303,757.40
	Floor Finishings Supply and install approved High traffic carpet laid on screeded levelled floor finish surface including necessary underlay and fittings to designer details.	0	m ²		-
	Supply and install approved spanish tiles on existing levelled floor finish surface to specifications	0	m ²		-
	Sub-total Floor Finishings				-
	Wall Finishings <u>Wood Panelling</u> 25mm MDF wood panelling on blockwall / concrete wall surfaces in approved triangular design with cove backlighting to approved standard and specification by project designer to include all necessary finishes	0	m ²		-
	Plant walls	0	m ²		-
	Alluminium sheet Cladding	0	m ²		-
	<u>Painting and Decorations</u> Prepare and apply one mist coat and full coats of "SHEEN" or other equal and approved paint on rendered surfaces including provision for wallpaper, stencil painting and murals paper	130	m ²		-
	INTERNAL POP Screeding Plaster of paris screed rendering on plastered block surfaces and drywalling; 2 coats, width exceeding 300mm, steel trowelled and sanding on completion	0	m ²		-
	<u>Art Works</u> Supply and installation of space-themed time travellers sculpture/mannequins of one 3D		Sum		
	<u>Skirting</u> 50mm high HDF wooden skirting	0	m		-
	Subtotal Wall Finishings				-
	Page/1				
ITEM	DESCRIPTION	QTY	UNIT	RATE	AMOUNT
	DEMO LAB <u>Ceiling Finishings</u> 9mm thick suspended gypsum board ceiling on galvanised steel framing; fixing to galvanised wire hangers,with tamper proof heads ; spot filling whole surface with slurry and sanded including POP surface screeding .	0	m ²		-
	Suspended wooden strips with plants	0	m ²		-
	Prepare and apply full coats of WHITE EMULSION" paint or other equal and approved paint on plasterboard soffit	0	m ²		-
	Subtotal Ceiling Finishings				-
	Furnitures and Fixtures 8-man workstation with acoustic panel divider and a storage cabinet	0	nr	4,053,878.70	-
	Executive Chairs	0	nr	403,367.41	-
	Writable Surface	30	m2	111,795.95	3,353,878.50
	Sub-total: Fittings and Fixtures				-
	<u>Lighting Luminaires</u> Suspended LED Circular lighting	0	nr		-
	Sub-total: Lighting Luminaires		nr		-
	<u>Plants</u> 5 foot indoor artiicial cedar topiary trees potted plants (two peace construction)	0	nr		-
	Sub-total: Lighting Luminaires				-
	Page/2				

ITEM	DESCRIPTION	QTY	UNIT	RATE	AMOUNT
	<u>DEMO LAB SUMMARY</u>				
AI	Internal Partitions				13,333,525.20
AII	Doors				5,303,757.40
B	Floor Finishings				-
C	Wall Finishings				-
D	Ceiling Finishings				-
E	Fittings and Fixtures				-
F	Lighting Luminaires				-
G	Plants				-
					-
	<u>DEMO LAB</u> Carried to MAIN SUMMARY				18,637,282.60
	Page/3				

ITEM	DESCRIPTION	QTY	UNIT	RATE	AMOUNT
	<u>INTERNAL FINISHINGS</u>				
	<u>INTERNAL WALL PARTITIONS</u>				
	<u>Sound Proof Walling</u>				
AI	100mm thick insulated soundproof partition drywalling framing built of galvanised steel framing, double faces of cement gypsum board with melamine-coating filling made of HD Rockwool to designer's specification		nr		-
	<u>Glass Partition</u>				
AII	2700mm high curtain wall with aluminium glazing frame of bronze anodized aluminium sections in approved colour, glazed with 8mm toughened/ laminated glass frosted to 1100mm height and other part maintained as plain glass including provision of sealant in the joints complete with all necessary fittings and accessories.		nr		-
	Internal partition to summary				-
	<u>Timber Door</u>				
Ai	900 x 2100mm single leaf, single swing 2 hours fire rated timber door finished in	0	nr		-
	<u>Glass Door</u>				
B	1000 x 2100mm high factory glazed aluminium double leaf door with 10mm thick plain frosted glass complete with all necessary fittings and accessories to specification	0	nr		-
	Sub-total Doors				-
	<u>Floor Finishings</u>				
Ci	Supply and install approved High traffic carpet laid on screeded levelled floor finish surface including necessary underlay and fittings to designer details.	0	m ²		-
Cii	Supply and install approved spanish tiles on existing levelled floor finish surface to specifications	205	m ²		-
	Sub-total Floor Finishings				-
D	<u>Wall Finishings</u>				
DI	<u>Wood Panelling</u>				
	25mm MDF wood panelling on blockwall / concrete wall surfaces in approved triangular design with cove backlighting to approved standard and specification by project designer to include all necessary finishes	0	m ²		-
	Plant walls	33	m ²		-
	Alluminium sheet Cladding	75	m ²		-
DII	<u>Painting and Decorations</u>				
s	Prepare and apply one mist coat and full coats of "SHEEN" or other equal and approved paint on rendered surfaces including provision for wallpaper, stencil painting and murals paper	50	m ²	35,231.18	1,761,559.00
DIII	<u>INTERNAL POP Screeding</u>				
	Plaster of paris screed rendering on plastered block surfaces and drywalling; 2 coats, width exceeding 300mm, steel trowelled and sanding on completion	50	m ²	33,731.18	1,686,559.00
DIV	<u>Photo Ops Wall / Artworks</u>				
	Supply and installation of PHOTO Ops stand complete with wooden frames, decorative lightngs, dark grey paint pattern on the wall and and artificial plants in line with the proposed Architectural design.		Sum		3,561,559.00
DV	<u>Skirting</u>				
	50mm high HDF wooden skirting	35	m		-
	Subtotal Wall Finishings				7,009,677.00
	Page/1				

ITEM	DESCRIPTION	QTY	UNIT	RATE	AMOUNT
	<u>COFFEE LOUNGE</u>				
AI	<u>Ceiling Finishings</u> 9mm thick suspended gypsum board ceiling on galvanised steel framing; fixing to galvanised wire hangers,with tamper proof heads ; spot filling whole surface with slurry and sanded including POP surface screeding .	105	m ²		-
AII	Suspended wooden strips with plants	105	m ²		-
B	Prepare and apply full coats of WHITE EMULSION" paint or other equal and approved paint on plasterboard soffit	105	m ²		-
	Subtotal Ceiling Finishings				-
C	<u>Furnitures and Fixtures</u>				
1	3- seater round table	2	nr	940,779.50	1,881,559.00
					-
2	3- seater round seaters	6	nr	325,259.83	1,951,558.98
					-
3	Coffee table	1	nr	1,706,558.98	1,706,558.98
					-
4	Coffee seats	4	nr	465,389.74	1,861,558.96
					-
5	8-seater high table	1	nr	2,021,558.96	2,021,558.96
					-
6	Burnt Orange Bar seats	8	nr	280,194.87	2,241,558.96
					-
7	Suspended wall storage (1675 x 1140mm)	2	nr	1,030,779.48	2,061,558.96
					-
8	Counter top storage	1	nr	1,881,558.98	1,881,558.98
					-
	Sub-total: Fittings and Fixtures				15,607,471.78
	<u>Lighting Luminaires</u>				
F	Suspended LED Circular lighting	12	nr		-
G			nr		-
	Sub-total: Lighting Luminaires				-
J	<u>Plants</u>				
1	5 foot indoor artiicial cedar topiary trees potted plants (two peace construction)	10	nr		-
	Sub-total: Lighting Luminaires				-
	Page/2				

ITEM	DESCRIPTION	QTY	UNIT	RATE	AMOUNT
	<u>COFFEE SUMMARY</u>				
AI	<u>Internal Partitions</u>				-
AII	Doors				-
B	Floor Finishings				-
C	Wall Finishings				7,009,677.00
D	Ceiling Finishings				-
E	Fittings and Fixtures				15,607,471.78
F	Lighting Luminaires				-
G	Plants				-
					-
	<u>COFFEE LOUNGE</u>				
	Carried to MAIN SUMMARY				22,617,148.78
	Page/3				

ITEM	DESCRIPTION	QTY	UNIT	RATE	AMOUNT
AI	INTERNAL FINISHINGS				
	INTERNAL WALL PARTITIONS				
	<u>Sound Proof Walling</u> 100mm thick insulated soundproof partition drywalling framing built of galvanised steel framing, double faces of cement gypsum board with melamine-coating filling made of HD Rockwool to designer's specification		nr		-
	<u>Glass Partition</u> 2700mm high curtain wall with aluminium glazing frame of bronze anodized aluminium sections in approved colour, glazed with 8mm toughened/ laminated glass frosted to 1100mm height and other part maintained as plain glass including provision of sealant in the joints complete with all necessary fittings and accessories.		nr		-
	Internal partition to summary				-
	<u>Timber Door</u> 900 x 2100mm single leaf, single swing 2 hours fire rated timber door finished in	0	nr		-
	<u>Glass Door</u> 1000 x 2100mm high factory glazed aluminium double leaf door with 10mm thick plain frosted glass complete with all necessary fittings and accessories to specification	0	nr		-
	Sub-total Doors				-
	Floor Finishings				
	Ci Supply and install approved High traffic carpet laid on screeded levelled floor finish surface including necessary underlay and fittings to designer details.	0	m²		-
	Cii Supply and install approved spanish tiles on existing levelled floor finish surface to specifications	205	m²		-
	Sub-total Floor Finishings				-
	D Wall Finishings				
	DI Wood Panelling 25mm MDF wood panelling on blockwall / concrete wall surfaces in approved triangular design with cove backlighting to approved standard and specification by project designer to include all necessary finishes	0	m²		-
	Plant walls	33	m²		-
	Alluminium sheet Cladding	75	m²		-
	DII Painting and Decorations Prepare and apply one mist coat and full coats of "SHEEN" or other equal and approved paint on rendered surfaces including provision for wallpaper, stencil painting and murals paper	130	m²		-
	DIII INTERNAL POP Screeding Plaster of paris screed rendering on plastered block surfaces and drywalling; 2 coats, width exceeding 300mm, steel trowelled and sanding on completion	130	m²		-
	DIV Art Works Supply and installation of space-themed time travellers sculpture/mannequins of one		Sum		17,453,878.68
	##### DV Skirting 50mm high HDF wooden skirting	35	m		-
	Subtotal Wall Finishings				17,453,878.68
	Page/1				
ITEM	DESCRIPTION	QTY	UNIT	RATE	AMOUNT
	EVENT HALL				
	AI Ceiling Finishings 9mm thick suspended gypsum board ceiling on galvanised steel framing; fixing to galvanised wire hangers,with tamper proof heads ; spot filling whole surface with slurrv and sanded including POP surface screeding .	105	m²		-
	AII Suspended wooden strips with plants	105	m²		-
	B Prepare and apply full coats of WHITE EMULSION" paint or other equal and approved paint on plasterboard soffit	105	m²		-
	Subtotal Ceiling Finishings				-
	C Furnitures and Fixtures				
	1 Speaker's Stand	1	nr	1,663,878.68	1,663,878.68
	2 Training Room Chairs	56	nr	250,000.00	14,000,000.00
	3 Regular seats in three different colours	150	nr	75,000.00	11,250,000.00
	4 Short poofs	4	nr	768,469.46	3,073,877.84
	5 Long poofs	2	nr	421,938.92	843,877.84
	Allow a provisional sum for wooden step seating in line with the Architect's design and Engineer's specifications		sum		10,907,755.68
	Sub-total: Fittings and Fixtures				41,739,390.04
	<u>Lighting Luminaires</u>				
	F Suspended LED Circular lighting	12	nr		-
	G		nr		-
	Sub-total: Lighting Luminaires				-
	J Plants				
	1 5 foot indoor artiicial cedar topiary trees potted plants (two peace construction)	10	nr		-
	Sub-total: Lighting Luminaires				-
	Page/2				

ITEM	DESCRIPTION	QTY	UNIT	RATE	AMOUNT
	<u>EVENT HALL SUMMARY</u>				
AI	Internal Partitions				-
AII	Doors				-
B	Floor Finishings				-
C	Wall Finishings				17,453,878.68
D	Ceiling Finishings				-
E	Fittings and Fixtures				41,739,390.04
F	Lighting Luminaires				-
G	Plants				-
					-
	<u>EVENT HALL</u>				
	Carried to MAIN SUMMARY				59,193,268.72
	Page/3				

ITEM	DESCRIPTION	QTY	UNIT	RATE	AMOUNT
	<u>INTERNAL FINISHINGS</u>				
	<u>INTERNAL WALL PARTITIONS</u>				
	<i><u>Sound Proof Walling</u></i>				
AI	100mm thick insulated soundproof partition drywalling framing built of galvanised steel framing, double faces of cement gypsum board with melamine-coating filling made of HD Rockwool to designer's specification	50	m ²		-
	<i><u>Glass Partition</u></i>				
AII	2700mm high curtain wall with aluminium glazing frame of bronze anodized aluminium sections in approved colour, glazed with 8mm toughened/ laminated glass frosted to 1100mm height and other part maintained as plain glass including provision of sealant in the joints complete with all necessary fittings and accessories.	50	nr		-
	Ditto: Regular patterned frosting	50	m2		-
	Internal partition to summary				-
	<u>CONFERENCE ROOM</u>				
	<i><u>Timber Door</u></i>				
Ai	900 x 2100mm single leaf, single swing 2 hours fire rated timber door finished in	0	nr		-
	<i><u>Glass Door</u></i>				
Bi	1000 x 2100mm high factory glazed aluminium double leaf door with 10mm thick plain frosted glass complete with all necessary fittings and accessories to specification	2	nr		-
	Sub-total Doors				-
	<u>Floor Finishings</u>				
Ci	Supply and install approved High traffic carpet laid on screeded levelled floor finish surface including necessary underlay and fittings to designer details.	260	m ²		-
	Sub-total Floor Finishings				-
D	<u>Wall Finishings</u>				
DI	<u>Wood Panelling</u>				
	25mm MDF wood panelling on blockwall / concrete wall surfaces in approved triangular design with cove backlighting to approved standard and specification by project designer to include all necessary finishes	86	m ²		-
DII	<u>Painting and Decorations</u>				
	Prepare and apply one mist coat and full coats of "SHEEN" or other equal and approved paint on rendered surfaces including provision for wallpaper, stencil painting and murals paper	230	m ²		-
s	<u>INTERNAL POP Screeding</u>				
	Plaster of paris screed rendering on plastered block surfaces and drywalling; 2 coats, width exceeding 300mm, steel trowelled and sanding on completion	230	m ²		-
DIV	<u>Art Works</u>				
	Supply and installation of space-themed time travellers sculpture/mannequins of one		Sum		11,394,287.74
DV	<u>Skirting</u>				
	50mm high HDF wooden skirting	60	m		-
	Subtotal Wall Finishings				11,394,287.74
	Page/1				

ITEM	DESCRIPTION	QTY	UNIT	RATE	AMOUNT
	<u>CONFERENCE ROOM Cont'd</u>				
AI	<u>Ceiling Finishings</u> 9mm thick suspended gypsum board ceiling on galvanised steel framing; fixing to galvanised wire hangers,with tamper proof heads ; spot filling whole surface with slurry and sanded including POP surface screeding .	140	m ²		-
AII	Suspended wooden strips	128	m ²		-
B	Prepare and apply full coats of WHITE EMULSION" paint or other equal and approved paint on plasterboard soffit	140	m ²		-
	Subtotal Ceiling Finishings				-
C	<u>Furnitures and Fixtures</u> Node seats in three different colours	0	nr		-
	Regular chairs	100	nr	103,825.85	10,382,585.00
	Speaker's seat	1	nr	1,504,287.05	1,504,287.05
	Speaker's stand	1	nr	889,287.05	889,287.05
	Sub-total: Fittings and Fixtures				12,776,159.10
	<u>Lighting Luminaires</u> Suspended LED Circular lighting	12	nr		-
	Sub-total: Lighting Luminaires				-
F	<u>Plants</u> Circular ceramic potted plant	5	nr		-
	Sub-total: Plants				-
	Page/2				

ITEM	DESCRIPTION	QTY	UNIT	RATE	AMOUNT
	<u>CONFERENCE ROOM SUMMARY</u>				
AI	Internal Partitions				-
AII	Doors				-
B	Floor Finishings				-
C	Wall Finishings				11,394,287.74
D	Ceiling Finishings				-
E	Fittings and Fixtures				12,776,159.10
F	Lighting Luminaires				-
G	Plants				-
					-
	CONFERENCE ROOM				
	Carried to MAIN SUMMARY				24,170,446.84
	Page/3				

ITEM	DESCRIPTION	QTY	UNIT	RATE	AMOUNT
	<u>INTERNAL FINISHINGS</u>				
	<u>INTERNAL WALL PARTITIONS</u>				
	<u>Sound Proof Walling</u>				
AI	100mm thick insulated soundproof partition drywalling framing built of galvanised steel framing, double faces of cement gypsum board with melamine-coating filling made of HD Rockwool to designer's specification	15	m ²	171,514.33	2,572,714.95
	<u>Glass Partition</u>				
AII	2700mm high curtain wall with aluminium glazing frame of bronze anodized aluminium sections in approved colour, glazed with 8mm toughened/ laminated glass frosted to 1100mm height and other part maintained as plain glass including provision of sealant in the joints complete with all necessary fittings and accessories.	25	m ²	249,352.78	6,233,819.50
	Ditto: Regular patterned frosting	25	m2	98,708.59	2,467,714.75
	Internal partition to summary				11,274,249.20
	<u>MEETING ROOMS</u>				
	<u>Timber Door</u>				
Ai	900 x 2100mm single leaf, single swing 2 hours fire rated timber door finished in	0	nr		-
	<u>Glass Door</u>				
Bi	900 x 2100mm high factory glazed aluminium double leaf door with 10mm thick plain frosted glass complete with all necessary fittings and accessories to specification	1	nr	2,117,714.75	2,117,714.75
	Ditto: Regular patterned frosting	2	m2	98,708.59	197,417.18
	Sub-total Doors				2,315,131.93
	<u>Floor Finishings</u>				
Ci	Supply and install approved laminate flooring on screeded levelled floor finish surface including necessary underlay and fittings to designer details.	0	m ²		-
Cii	Supply and install approved high traffic carpet on existing levelled floor finish surface to specifications	0	m ²		-
	Sub-total Floor Finishings				-
D	<u>Wall Finishings</u>				
DI	<u>Wood Panelling</u>				
	25mm MDF wood panelling on blockwall / concrete wall surfaces in approved triangular design with cove backlighting to approved standard and specification by project designer to include all necessary finishes	0	m ²		-
DII	<u>Painting and Decorations</u>				
s	Prepare and apply one mist coat and full coats of "SHEEN" or other equal and approved paint on rendered surfaces including provision for wallpaper, stencil painting and murals paper	30	m ²	61,257.16	1,837,714.80
DIII	<u>INTERNAL POP Screeding</u>				
	Plaster of paris screed rendering on plastered block surfaces and drywalling; 2 coats, width exceeding 300mm, steel trowelled and sanding on completion	30	m ²	59,757.16	1,792,714.80
DIV	<u>Art Works</u>				
	Supply and installation of space-themed time travellers sculpture/mannequins of one 3D spaceman to 1759 mm height and two helmets fixed firm on prefinished wall surface in accordance to proposed design and details		Sum		
#####					
DV	<u>Skirting</u>				
	50mm high HDF wooden skirting	0	m		-
	Subtotal Wall Finishings				3,630,429.60
	Page/1				

[illegible]

ITEM	DESCRIPTION	QTY	UNIT	RATE	AMOUNT
	<u>INTERNAL FINISHINGS</u>				
	INTERNAL WALL PARTITIONS				
	<u>Sound Proof Walling</u>				
AI	100mm thick insulated soundproof partition movable collapsible drywalling partition with rollers, framing built of galvanised steel framing, double faces of cement gypsum board with melamine-coating filling made of HD Rockwool to designer's specification	0	m ²		-
	<u>Glass Partition</u>				
AII	2700mm high curtain wall with aluminium glazing frame of bronze anodized aluminium sections in approved colour, glazed with 8mm toughened/ laminated glass frosted to 1100mm height and other part maintained as plain glass including provision of sealant in the joints complete with all necessary fittings and accessories.	0	m ²		-
	Ditto: Regular patterned frosting	0	m2		-
	Internal partition to summary				-
	<u>STAFF OFFICE</u>				
	<u>Timber Door</u>				
Ai	900 x 2100mm single leaf, single swing 2 hours fire rated timber door finished in		nr		-
	<u>Glass Door</u>				
B	1000 x 2100mm high factory glazed aluminium double leaf door with 10mm thick plain frosted glass complete with all necessary fittings and accessories to specification	0	nr		-
	Sub-total Doors				-
	<u>Floor Finishings</u>				
Ci	Supply and install approved High traffic carpet laid on screeded levelled floor finish surface including necessary underlay and fittings to designer details.	21	m ²		-
Cii	Supply and install approved laminate flooring on existing levelled floor finish surface	21	m ²		-
	Sub-total Floor Finishings				-
D	<u>Wall Finishings</u>				
DI	<u>Wood Panelling</u>				
	25mm MDF wood panelling on blockwall / concrete wall surfaces in approved triangular design with cove backlighting to approved standard and specification by project designer to include all necessary finishes	34	m ²		-
	Steel Cladding	34	m ²		-
s	<u>Painting and Decorations</u>				
	Prepare and apply one mist coat and full coats of "SHEEN" or other equal and approved paint on rendered surfaces including provision for wallpaper, stencil painting and murals paper	60	m ²		-
DIII	<u>INTERNAL POP Screeding</u>				
	Plaster of paris screed rendering on plastered block surfaces and drywalling; 2 coats, width exceeding 300mm, steel trowelled and sanding on completion	60	m ²		-
DIV	<u>Art Works</u>				
	Supply and installation of space-themed time travellers sculpture/mannequins of one		Sum		4,653,878.71
DV	<u>Skirting</u>				
	50mm high HDF wooden skirting	35	m		-
	Subtotal Wall Finishings				4,653,878.71
	Page/1				

ITEM	DESCRIPTION	QTY	UNIT	RATE	AMOUNT
	<u>OFFICE2.</u>				
AI	<u>Ceiling Finishings</u> 9mm thick suspended gypsum board ceiling on galvanised steel framing; fixing to galvanised wire hangers,with tamper proof heads ; spot filling whole surface with slurry and sanded including POP surface screeding .	23	m ²		-
AII	Suspended wooden strips	21	m ²		-
B	Prepare and apply full coats of WHITE EMULSION" paint or other equal and approved paint on plasterboard soffit	23	m ²		-
	Subtotal Ceiling Finishings				-
C	<u>Furnitures and Fixtures</u>				
1	8-man Long Desk	2	nr	3,226,939.35	6,453,878.70
2	Task Chairs	16	nr	278,367.41	4,453,878.56
3	Side Storage	16	nr	228,367.41	3,653,878.56
4	2-man Booth	2	nr	2,126,939.28	4,253,878.56
5	Print bay console (1850 X 450mm)	1	nr	2,773,878.56	2,773,878.56
6	Acoustic panel divider for the work station	2	nr	1,276,939.28	2,553,878.56
	Sub-total: Fittings and Fixtures				24,143,271.50
	Page/2				

ITEM	DESCRIPTION	QTY	UNIT	RATE	AMOUNT
	<u>OFFICE.2 SUMMARY</u>				
AI	Internal Partitions				-
AII	Doors				-
B	Floor Finishings				-
C	Wall Finishings				4,653,878.71
D	Ceiling Finishings				-
E	Fittings and Fixtures				24,143,271.50
					-
	<u>OFFICE 2</u>				
	Carried to MAIN SUMMARY				28,797,150.21
	Page/3				

ITEM	DESCRIPTION	QTY	UNIT	RATE	AMOUNT
	<u>INTERNAL FINISHINGS</u>				
	<u>INTERNAL WALL PARTITIONS</u>				
	<u>Sound Proof Walling</u>				
AI	100mm thick insulated soundproof partition movable collapsible drywalling partition with rollers, framing built of galvanised steel framing, double faces of cement gypsum board with melamine-coating filling made of HD Rockwool to designer's specification	151.34	m ²	62,675.02	9,485,237.53
	<u>Glass Partition</u>				
AII	2700mm high curtain wall with aluminium glazing frame of bronze anodized aluminium sections in approved colour, glazed with 8mm toughened/ laminated glass frosted to 1100mm height and other part maintained as plain glass including provision of sealant in the joints complete with all necessary fittings and accessories.	152.9	m ²	186,261.30	28,479,352.77
	Ditto: Regular patterned frosting	152.9	m2	35,617.11	5,445,856.12
	Internal partition to summary				43,410,446.42
	<u>MANAGEMENT'S OFFICE</u>				
	<u>Timber Door</u>				
Ai	900 x 2100mm single leaf, single swing 2 hours fire rated timber door finished in		nr		-
	<u>Glass Door</u>				
B	1200 x 2100mm high factory glazed aluminium double leaf door with 10mm thick plain frosted glass complete with all necessary fittings and accessories to Architect's specifications	1	nr	458,856.11	458,856.11
	Ditto; size 900 x 2100mm	4	nr	364,714.02	1,458,856.08
	Ditto: Regular patterned frosting	11	m2	108,077.95	1,188,857.45
	Sub-total Doors				1,917,712.19
	<u>Floor Finishings</u>				
Ci	Supply and install approved High traffic carpet laid on screeded levelled floor finish surface including necessary underlay and fittings to designer details.	0	m ²		-
Cii	Supply and install approved laminate flooring on existing levelled floor finish surface	0	m ²		-
	Sub-total Floor Finishings				-
D	<u>Wall Finishings</u>				
DI	<u>Wood Panelling</u>				
	25mm MDF wood panelling on blockwall / concrete wall surfaces in approved triangular design with cove backlighting to approved standard and specification by project designer to include all necessary finishes	0	m ²		-
	Steel Cladding	0	m ²		-
s	<u>Painting and Decorations</u>				
	Prepare and apply one mist coat and full coats of "SHEEN" or other equal and approved paint on rendered surfaces including provision for wallpaper, stencil painting and murals paper	169.64	m ²	9,062.82	1,537,416.78
DIII	<u>INTERNAL POP Screeding</u>				
	Plaster of paris screed rendering on plastered block surfaces and drywalling; 2 coats, width exceeding 300mm, steel trowelled and sanding on completion	169.64	m ²	7,562.82	1,282,956.78
DIV	<u>Art Works</u>				
	Supply and installation of space-themed time travellers sculpture/mannequins of one		Sum		
DV	<u>Skirting</u>				
	50mm high HDF wooden skirting	0	m		-
	Subtotal Wall Finishings				2,820,373.57
	Page/1				

ITEM	DESCRIPTION	QTY	UNIT	RATE	AMOUNT
	<u>MANAGEMENT'S OFFICE.</u>				
AI	<u>Ceiling Finishings</u> 9mm thick suspended gypsum board ceiling on galvanised steel framing; fixing to galvanised wire hangers,with tamper proof heads ; spot filling whole surface with slurry and sanded including POP surface screeding .	114.95	m ²	27,471.56	3,157,855.82
AII	Suspended wooden strips	0	m ²		-
B	Prepare and apply full coats of WHITE EMULSION" paint or other equal and approved paint on plasterboard soffit	114.95	m ²	9,971.56	1,146,230.82
	Subtotal Ceiling Finishings				4,304,086.64
C	<u>Furnitures and Fixtures</u>				
1	Executive Table	3	nr	776,285.27	2,328,855.81
2	Executive Chairs	3	nr	536,285.27	1,608,855.81
3	Guest Seat	3	nr	436,285.27	1,308,855.81
4	Office Executive Couch	1	nr	1,358,855.81	1,358,855.81
5	Main Executive Table with Side Storage	1	nr	1,408,855.81	1,408,855.81
6	Executive Chair	1	nr	1,208,855.81	1,208,855.81
7	Guest Seats	2	nr	579,427.90	1,158,855.80
8	Writable surface		sum		-
9	Side Worktop	1	nr	1,008,855.80	1,008,855.80
10	White HDF Console	3	nr	636,285.26	1,908,855.78
11	Allow a provisional sum for a structural steel frame for the glass partition complete with all other accessories for complete installation in line with the Engineer's instruction		sum		5,858,855.78
	Sub-total: Fittings and Fixtures				19,158,558.02
	<u>Lighting Luminaires</u>				
F	Suspended LED Circular lighting	6	nr		-
G					-
	Sub-total: Lighting Luminaires				-
J	<u>Plants</u>				
1	1500mm x 450mm intergrated plants on booth seating.	6	nr		-
	Sub-total: Plants				-
	Page/2				

ITEM	DESCRIPTION	QTY	UNIT	RATE	AMOUNT
	<u>MANAGEMENT OFFICE. SUMMARY</u>				
AI	Internal Partitions				43,410,446.42
AII	Doors				1,917,712.19
B	Floor Finishings				-
C	Wall Finishings				2,820,373.57
D	Ceiling Finishings				4,304,086.64
E	Fittings and Fixtures				19,158,558.02
F	Lighting Luminaires				-
G	Plants				-
					-
	<u>MANAGEMENT OFFICE</u>				
	Carried to MAIN SUMMARY				71,611,176.84
	Page/3				

ITEM	DESCRIPTION	QTY	UNIT	RATE	AMOUNT
	<u>INTERNAL FINISHINGS</u>				
	<u>INTERNAL WALL PARTITIONS</u>				
	<u>Sound Proof Walling</u>				
AI	100mm thick insulated soundproof partition movable collapsible drywalling partition with rollers, framing built of galvanised steel framing, double faces of cement gypsum board with melamine-coating filling made of HD Rockwool to designer's specification	0	m ²	62,675.02	-
	<u>Glass Partition</u>				
AII	2700mm high curtain wall with aluminium glazing frame of bronze anodized aluminium sections in approved colour, glazed with 8mm toughened/ laminated glass frosted to 1100mm height and other part maintained as plain glass including provision of sealant in the joints complete with all necessary fittings and accessories.	0	m ²	186,261.30	-
	Ditto: Regular patterned frosting	0	m2	35,617.11	-
	Internal partition to summary				-
	<u>GENERAL WORKSPACE</u>				
	<u>Timber Door</u>				
Ai	900 x 2100mm single leaf, single swing 2 hours fire rated timber door finished in		nr		-
	<u>Glass Door</u>				
B	1200 x 2100mm high factory glazed aluminium double leaf door with 10mm thick plain frosted glass complete with all necessary fittings and accessories to Architect's specifications	0	nr	1,258,856.11	-
	Ditto; size 900 x 2100mm	0	nr	564,714.02	-
	Ditto: Regular patterned frosting	0	m2	108,077.95	-
	Sub-total Doors				-
	<u>Floor Finishings</u>				
Ci	Supply and install approved High traffic carpet laid on screeded levelled floor finish surface including necessary underlay and fittings to designer details.	0	m ²		-
Cii	Supply and install approved laminate flooring on existing levelled floor finish surface	0	m ²		-
	Sub-total Floor Finishings				-
D	<u>Wall Finishings</u>				
DI	<u>Wood Panelling</u>				
	25mm MDF wood panelling on blockwall / concrete wall surfaces in approved triangular design with cove backlighting to approved standard and specification by project designer to include all necessary finishes	0	m ²		-
	Steel Cladding	0	m ²		-
s	<u>Painting and Decorations</u>				
	Prepare and apply one mist coat and full coats of "SHEEN" or other equal and approved paint on rendered surfaces including provision for wallpaper, stencil painting and murals paper	0	m ²	9,062.82	-
DIII	<u>INTERNAL POP Screeding</u>				
	Plaster of paris screed rendering on plastered block surfaces and drywalling; 2 coats, width exceeding 300mm, steel trowelled and sanding on completion	0	m ²	7,562.82	-
DIV	<u>Art Works</u>				
	Supply and installation of space-themed time travellers sculpture/mannequins of one		Sum		
DV	<u>Skirting</u>				
	50mm high HDF wooden skirting	0	m		-
	Subtotal Wall Finishings				-
	Page/1				

ITEM	DESCRIPTION	QTY	UNIT	RATE	AMOUNT
	<u>GENERAL WORKSPACE</u>				
AI	<u>Ceiling Finishings</u> 9mm thick suspended gypsum board ceiling on galvanised steel framing; fixing to galvanised wire hangers,with tamper proof heads ; spot filling whole surface with slurry and sanded including POP surface screeding .	0	m ²	27,471.56	-
AII	Suspended wooden strips	0	m ²		-
B	Prepare and apply full coats of WHITE EMULSION" paint or other equal and approved paint on plasterboard soffit	0	m ²	9,971.56	-
	Subtotal Ceiling Finishings				-
C	<u>Furnitures and Fixtures</u> 10-man workstation with acoustic dividers and storage cabinet in line with Architect's details and specifications	4	nr	4,500,000.00	18,000,000.00
1					
2	Workstation chairs	40	nrs	278,367.41	11,134,696.40
	Sub-total: Fittings and Fixtures				29,134,696.40
	Page/2				
ITEM	DESCRIPTION	QTY	UNIT	RATE	AMOUNT
	<u>GENERAL WORKSPACE SUMMARY</u>				
AI	Internal Partitions				-
AII	Doors				-
B	Floor Finishings				-
C	Wall Finishings				-
D	Ceiling Finishings				-
E	Fittings and Fixtures				29,134,696.40
F	Lighting Luminaires				
G	Plants				-
	<u>GENERAL WORKSPACE</u> Carried to MAIN SUMMARY				29,134,696.40
	Page/3				